Group of Engineers, Architects & Contractors

CONTACT NO.: 94253 8680, 62684 53181 -MAIL: infra.mould@gmail.com



Dear Sir,

Thank you for your inquiry for Construct your dream home. We provide comprehensive turnkey solutions, handling everything from design and planning to construction and final delivery. Our clients enjoy a hassle-free experience from start to finish. We will deliver your house to you as per the specification given below without any manipulation. We sincerely hope that you will give us a chance to construct your home.

OUR COMMITMENT:

Quality Assurance: We adhere to the highest quality standards, using the finest materials and cutting-edge
construction techniques to ensure longevity and durability in every project.
Innovation: Inframould embraces innovation and sustainability. We constantly seek new technologies and
eco-friendly practices to reduce our environmental footprint and enhance the efficiency of our work.
<u>Customer-Centric Approach:</u> Our clients are at the heart of everything we do. We listen, collaborate, and
adapt to their needs, ensuring that every project reflects their vision.
<u>Professionalism:</u> We pride ourselves on our professionalism and transparency. Our projects are completed

on time and within budget, and we maintain clear communication throughout the construction process.

Contact no. 94253 86860, 62684 53181, e-Mail: infra.mould@gmail.com

Specification & scope of G+1 House Construction @ 2050 per sq. ft.

NFRAMOULD

Design & Drawings

- Floor Plans
- > 3D Elevation
- ➤ MEP Drawings
- Working Drawings
- Structural Drawings

Structure Work

- > Foundation
- > Foundation depth
- Under ground Tank
- > Anti Termite Treat
- > Plinth Height
- Ceiling height
- > Steel Reinforcement
- Cement
- > P.C.C. Grade
- > R.C.C. Grade
- Bricks in Super Structure
- ➤ Internal Plaster
- > External Plaster
- ➤ Window Grills

Flooring Work

- Rooms, Kitchen, Dining, balcony floor
- ➤ Kitchen Dado Tiles
- Rooms Skirting

- > 2D Floor Plans with Furniture layout
- Front 3D Elevation
- Plumbing & electrical
- > For execution of work
- > As per design
- Isolated footing
- Maximum 10 foot from road level
- > 6000 Ltr in 4" BW+4" RCC
- > In plinth
- Maximum 1.5 foot from Road level
- > 10.5 foot from floor to floor
- > Fe500 Moira, Goyal or Equivalent
- Ultratech, JK Super or Equivalent
- > M-10 (1:3:6)
- ➤ M-20 (1:1.5:3)
- ➤ 4" thick internal & 8" thick External walls using Good quality open Bhatta red brick (4" X 4" X 8")
- Double coat in 1:4 Cement mortar
- Double coat in 1:4 Cement Mortar mixing dr. fixit LW+ chemical
- MS bright Bar grill in External windows
- 2' X 4' Vitrified Tiles @ 85/sqft (Make : AGL, Kajaria or Equivalent)
- ▶ 2' height 2' X 4' Vitrified Tiles @ 80/sqft (Make : AGL, Kajaria or Equiva)
- > 5" height in same floor Tile

Flooring Work

- ➤ Parking Tiles
- > Stair Case Trade
- Staircase Riser, Skirting and Landing
- Toilet & Wash Area floor Tiles
- ➤ Toilet Dado (Wall)
 Tiles
- Wash Area Dado (Wall) Tiles
- > Kitchen Counter

Plumbing

- CPVC Pipe Lines
- > SWR/ PVC Pipe Lines
- Over Head Water Tank

- 2' X 2' Antiskid Tiles @ 60/sqft (Make : AGL, Kajaria or Equivalent)
- Granite with front and side molding polishing @ 180/sqft
- Granite with front and side molding polishing
- 2' X 2' Antiskid Tiles @ 100/sqft (Make : AGL, Kajaria or Equivalent)
- 2' X 4' Vitrified Tiles Upto 7' height @ 80/sqft (Make : AGL, Kajaria or Equivalent)
- 2' X 4' Vitrified Tiles Upto 10' height
 80/sqft (Make : AGL, Kajaria or Equivalent)
- Granite over Kota Stone with front side double Patti molding & Polishing (Maximum 20 RFT). Granite @ 160/sqft
- Use 0.75" to 2" dia. CPVC Pipes as per required (Make: Astral, Ashirwad, Supreme or Equivalent)
- Use 1.25" to 6" dia. SWR Pipes for Drainage and Rain water line as per required (Make: Astral, Ashirwad, Supreme or Equivalent)
- Water > 5 Layered 1500 Ltr. Water Tank (Make: Sintex, Plasto or equivalent)

Contact no. 94253 86860 , 62684 53181, e-Mail: infra.mould@gmail.com

Specification & scope of G+1 House Construction @ 2050 per sq. ft.

Bath Fittings		Door	
➤ Make	➤ Jaquar or Equivalent	➤ Internal Doors	plywood paneling with mica frame suitable for 3' X 7' opening.
Accessories in Each	➤ One EWC with Seat Cover & Open		
Toilet	Flush Tank		Flush door with mica and SS Finish
	One Health Faucet		accessories (Total Cost Upto
	One Two way Bib Cock		17000).
	One Wall Mounted Wash Basin with Pillar Cock	➤ Toilet Doors	➢ PVC/Granite Door Frame suitable for 2'6" x 7' opening.
	One Wall Mixer with Shower		➤ PVC/ Flush Door with Mica or
	➤ Angle Cock for Geyser, Basin &		Equivalent (Total Cost Upto 10000).
Manager and the second of the	Flush Tank	Terrace Door	➤ MS Fabricated door suitable for 3' X
	Approximate budget for Each Toilet		7' opening.
	is Rs. 35000/ Toilet	Parking Door	MS Fabricated door suitable for 10'
➤ Other Taps	> One Bib cock with Nozzle for		X 5' opening.
	Washing Machine and One for Parking (Rs, 1300/ each)	Safety Door	MS door with SS Mesh
	➤ One Bib cock without nozzle in	Windows	
	wash area and one on Terrace (Rs,	Windows (Area Upto	> 2.5 Track UPVC window (2 glass
	1300/ each)	10% of Built-up	and 1 mesh) with Granite Jamming.
Kitchen Sink	Stainless Steel Sink with sink Cock (Upto Rs. 9500/ Each Set)	Area.)	(Upto Rs. 700/sqft)
Name of the state		Windows Grill	Provide in all external window in
Doors			MS Square Bright bar
➤ Main Door	➤ 6"x2.5" double patam plywood		
	paneling with veneer frame suitable	Fabrications	
	for 3'3" X 7' opening.	➤ MS Fabrications	Maximum 300 kg / 1000 sqft of
	➤ Flush door with venner/teakwood	,	built-up area for Window Grill, MS
	and SS Finish accessories (Total		Gate, Head room Door, OTS Cover,
	Cost Upto 30000).		Ladder etc.

Contact no. 94253 86860, 62684 53181, e-Mail: infra.mould@gmail.com

Specification & scope of G+1 House Construction @ 2050 per sq. ft.

Electrical Work Wiring and Cabling Work. Inverter Line

Switches/ Sockets

- Earthing

- > ISI Marked copper wire for all internal work from Meter/MCCB Box to individual points. Use different type wire ei. 0.75/1/1.5/2/2.5 sq. mm wire as required in different color code. (Make: Polycab, RR or Equivalent)
- ➤ ISI Marked 16 sqmm 4 core aluminum armored cable from Meter/ MCCB Box to Electric Board Supply feeder (Maximum 40 rft) (Make: Polycab, RR or Equivalent)
- > Laying 1 sq. mm copper wiring from inverter to one switch board in each room.
- > Use ISI Marked Modular switches. switch plats, sockets etc. with minimum two year warranty. (Make: Western Vega, Anchor Equivalent). Cost Upto Rs. 60 / Each.
- > Camera & Net Points > Provide cat 6 cable from center point to each room and 8 Camera points at required location.
 - Install one chemical earthing for entire home.

Painting Work

Internal Wall Painting

- Paint on Fabrication
- External Wall **Painting**

Other Works

- Compound > Front Wall under Built-up area only
- > Toilet Waterproofing
- > Terrace Waterproofing
- Balcony Railing
- > Stair Railing

- > Two coat wall putty on Wall and one coat Acrylic putty on Wall (Make: Birla or Equivalent)
- > One coat interior Grade Primer & Two coat interior Grade Paint on Wall (Make: Asian Royal Shyne or Equivalent)
- > One Coat Epoxy metal Primer and Two Coat Epoxy Paint (Make: Asian Apcolite Epoxy or Equivalent)
- One Coat Exterior Primer & Two Coat Exterior Paint (Make: Asian Ultima Exterior Emulsion Equivalent)
- > Design as per elevation Upto 10 RFT & 5 foot Height.
- > Brickbat Coba with 2 coat URP Coating.
- > Apply two coat Dr. fixit fastflex Coating and Brickbat coba mixing LW+ Chemical
- > 12 mm Toughened glass with wooden finish top rail. Upto Rs. 1600 per RFT
- > 12 mm Toughened glass with wooden finish top rail. Upto Rs. 1800 per RFT

Contact no. 94253 86860 , 62684 53181, e-Mail: infra.mould@gmail.com



Other Terms and Conditions

Septic tank, soak pit, Circular/Helical staircase & Lift, Safety doors, Electrical fixtures, Solar System (Electric & Water) & DG Back up, Video Door Phone with intercom, Furniture work, Rain water harvesting, AC Copper Conduiting line work, Water Pump, Pressure Pump, RO, Water softener, Name Plate, SS Lettering, glass bath-Shower partition, Bath Tub, Home Automation, Terrace Flooring, Tiles in Water tank, Gas line, Special Elevation Features (Deviations from standard Architectural Elevation) area, Ceiling Haller Design, Interior Designs, Landscaping works, Plinth Protection across boundary, back filling outside built up area, back filling above specified Limit, any construction out side the built-up area(i.e. Setback area slab, Boundary wall etc.) and any other Work which is not mentioned in the selected package list are excluded from our scope (not included in the scope of Inframould). if customer want to do any thing from this,
than extra charges will be bear by Plot owner.
Site Clearance, Plot demarcation, Drawings and its approvals, Water & electricity connections, Any other approvals from govt. or developers etc. in the scope of Plot owner.
Staircase would be waist slab type and Dimension- Width-3.25 feet, Tread-10 inch, Riser-7 inch Steps would be casted in RCC. Any other type stair (i.e. Helical/Circular etc.) case are not cover in scope of Inframould construction. Only 1 staircase considered for entire house.
In case there is no space for storage of Bulk Raw Materials with in a lead of 15 Meter from the work site then it shall be charged extra on the selected package.
The final price would depend on the actual materials and design specifications decided by the customer.

Payment Conditions

	2002 200 3		
☐ At the time of Work or <mark>der or</mark> Agreement	- 05 %	Against Completion of First floor Internal Plaster	- 03 %
☐ Against Delivery of Sand Aggregate and Steel at Site	- 05 %	☐ Against Completion of External Plaster	- 04%
Against Completion of plinth slab	- 09 %	□ Against Completion of Doors and Windows	- 08 %
Against Completion of plinth slab	- 05 %	Against Completion of Painting and Electrical Works	- 10 %
☐ Against Completion of Ground floor roof Slab	- 13 %	□ Against Delivery of Flooring Material	- 08 %
☐ Against Completion of First Floor Brick Work	- 05 %	☐ Against Completion of Flooring work	- 03 %
☐ Against Completion of First floor roof Slab	- 13 %	Against Completion of CP Sanitary work	- 07 %
Against Completion of Ground floor Internal Plaster	- 03 %	☐ At the time of/Before Possession	- 01 %